

CONTENTS

	Page no.
List of Abbreviation	vii
List of Figures	viii
List of Tables	ix
Chapter 1	1
1.0 Introduction	1
Chapter 2	3
2.0 Energy from sun	3
2.1 Routes for converting solar energy into electrical energy	3
2.2 Photovoltaic system for electrification	4
2.2.1 Standalone SPV system/Decentralized SPV Systems	4
2.2.2 Grid connected photovoltaic system	5
2.3 System design parameters	6
2.4 Battery bank	7
2.5 Charge controller	9
2.6 Inverter	10
2.7 Solar mobile charging station	10
2.7.1 Specification	11
Chapter 3	13
3.0 Literature Review	13
Chapter 4	23
4.0 Research objectives	23
4.1 Research Methodology	24
Chapter 5	28
5.0 Technical-Socio-Economic evaluation of SMCF	28
5.1 System design considerations	28
5.1.1 Technical performance of SMCF based on overall study	28

5.2	Socio-Economic evaluation of SMCF	32
5.2.1	Functionality	32
5.2.2	System performance	35
5.2.3	System cost and financial structure	38
5.2.4	Institutional Structure	40
5.2.5	Impact assessment	41
5.2.6	Revenue generation	43
5.2.7	Financial model acceptability of SMCF based on LLM	46
5.2.8	Fault assessment	48
5.2.9	Role of PIA	49
5.2.10	Monitoring and Maintenance	50
5.3	Impact of SMCF	52
5.4	Susceptive models	55
5.5	PV Standalone system	55
5.5.1	PV standalone system components	56
5.6	BTS-Load	57
5.6.1	Calculations for component sizing for standalone PV system	58
5.7	PV-DG Hybrid	61
5.7.1	Components used in PV-DG Hybrid	61
5.7.2	Charge controller design for PV-DG Hybrid system	64
6.0	Recommendation and conclusion	67
6.1	Future work scope	69
	Reference	70
	Annexure 1	74
	Annexure 2	76
	Annexure 3	79
	Annexure 4	80

LIST OF ABBREVIATIONS

BTS	Base transceiver station
USO	Universal service obligations
DOT	Department of telecommunication
LaBL	Lightning a Billion Lives
SHS	Solar Home System
MNES	Ministry of Non-Conventional Energy Sources
TRAI	Telecom Regulatory Authority of India
USOF	Universal service obligation fund
SMCS	Solar mobile charging station
SMCF	Solar mobile charging facilities
TERI	The Energy Research Institute
RESCO	Renewable Energy Service Company
SPV	Solar Photovoltaic
Isc	Short circuit current of PV module
Voc	Open circuit voltage of PV module
Imp	Current at Maximum Power of PV module
Vmp	Voltage at Maximum Power of PV module
CSCS	Centralized Solar Charging Station
BOS	Balance of system
BTS	Base transceiver station

LIST OF FIGURES

		Page no.
Figure 1.1	Standalone Photovoltaic System	5
Figure 1.2	Grid connected photovoltaic system	6
Figure 1.3	Charge controller	9
Figure 1.4	SMCS -prototype	10
Figure 1.5	Adopted survey topology	25
Figure 1.6	Survey mapping	26
Figure 1.7	Functionality of SMCS	34
Figure 1.8	Impact assessment of SMCS	41
Figure 1.9	Monthly revenue generation plot	45
Figure 1.10	Fault assessment of SMCS under USOF	48
Figure 1.11	Institutional model	49
Figure 1.12	Rise in teledensity	52
Figure 1.13	Demand for SMCS	53
Figure 1.14	Mobile facilities satisfaction level	53
Figure 1.15	Block diagram of PV Standalone system	56
Figure 1.16	Typical load diagram of an outdoor BTS site	58
Figure 1.17	Block diagram of PV- DG Hybrid System	62

LIST OF TABLES

		Page no.
Table1.1	Technical specification of SMCS	12
Table1.2	State wise detailed report	24
Table1.3	Operating load base analyses of SMCS	30
Table1.4	Result specific to case study of SMCS	31
Table1.5	Showcasing functionality of SMCS	33
Table1.6	System performance based on study	35
Table1.7	Village wise revenue generation	44
Table1.8	Financial acceptability based on breakeven analysis	47
Table1.9	Training initiative benefits in three states	51